

Editorial Manager(tm) for Structural Concrete  
Manuscript Draft

Manuscript Number:

Title: Belgrade's DELTA CITY shopping mall - design and construction

Article Type: Technical paper

Corresponding Author: Associate professor Snezana B Marinkovic, Ph.D

Corresponding Author's Institution: University of Belgrade, Faculty of Civil Engineering

First Author: Snezana B Marinkovic, Ph.D

Order of Authors: Snezana B Marinkovic, Ph.D; Veljko M Kokovic, MSc.; Ivan S Ignjatovic, MSc.; Vanja H Alendar, MSc.

**Abstract:** The structure of DELTA CITY shopping mall in Belgrade consists of two separated structures: the structure of the mall and the structure of the multi-story open garage. The overall dimensions of the irregular layout of the structure are 210 m x 120 m, with four main levels in the mall and five parking levels in the garage. Because of the different exposure conditions, the structure of the garage is separated from the mall's structure with an expansion joint at all the levels, except at the level of the foundation slab.

The mall's framed structure is designed without any expansion joints, except for temporary joints during the construction stage. It consists mainly of reinforced concrete cantilevered columns cast in place, at typical spans of 8.2 m x 8.2 m, precast reinforced concrete simple beams and precast prestressed hollow core slabs. The reinforced concrete frames cast in place are designed mostly at the façade, to provide additional seismic resistance and to control lateral deflections. The main structure of the open multi-story garage consists of reinforced concrete frames cast in place and precast hollow core slabs and it is designed for exposure class XD3, with special attention paying to durability requirements.

Due to mainly precast structure, especially hollow core slabs as a floor solution, the complete concrete structure of approximately 80000 m<sup>2</sup> was constructed for less than 12 months.

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

- Date written: 28-03-2009.
- Title: Belgrade's DELTA CITY shopping mall - design and construction
- Authors:  
Snežana B. Marinković\*, PhD.  
Associate Professor, Faculty of Civil Engineering, University of Belgrade, 11000 Belgrade, Serbia  
Veljko M. Koković, MSc.  
Assistant, Faculty of Civil Engineering, University of Belgrade, 11000 Belgrade, Serbia  
Ivan S. Ignjatović, MSc.  
Assistant, Faculty of Civil Engineering, University of Belgrade, 11000 Belgrade, Serbia  
Vanja H. Alendar, MSc.  
Technical Director, DN Engineering Consultants, 11000 Belgrade, Serbia

- \*Corresponding author:  
Snežana B. Marinković  
Faculty of Civil Engineering  
University of Belgrade  
Bul. kralja Aleksandra 73  
11000 Belgrade, Serbia  
e-mail: [snaska@imk.grf.bg.ac.yu](mailto:snaska@imk.grf.bg.ac.yu)  
Tel: + 381 11 3370 102  
Fax: + 381 11 3370 223

- Number of words: 4042
- Number of figures: 20
- Three key words: precast concrete structure, hollow core slabs, durability

1  
2  
3  
4  
5 **Abstract**  
6  
7  
8  
9

10 The structure of DELTA CITY shopping mall in Belgrade consists of two separated  
11 structures: the structure of the mall and the structure of the multi-story open garage. The  
12 overall dimensions of the irregular layout of the structure are 210 m x 120 m, with four  
13 main levels in the mall and five parking levels in the garage. Because of the different  
14 exposure conditions, the structure of the garage is separated from the mall's structure with  
15 an expansion joint at all the levels, except at the level of the foundation slab.  
16  
17  
18  
19  
20  
21  
22

23 The mall's framed structure is designed without any expansion joints, except for  
24 temporary joints during the construction stage. It consists mainly of reinforced concrete  
25 cantilevered columns cast in place, at typical spans of 8.2 m x 8.2 m, precast reinforced  
26 concrete simple beams and precast prestressed hollow core slabs. The reinforced  
27 concrete frames cast in place are designed mostly at the façade, to provide additional  
28 seismic resistance and to control lateral deflections. The main structure of the open multi-  
29 story garage consists of reinforced concrete frames cast in place and precast hollow core  
30 slabs and it is designed for exposure class XD3, with special attention paying to durability  
31 requirements.  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42

43 Due to mainly precast structure, especially hollow core slabs as a floor solution, the  
44 complete concrete structure of approximately 80000 m<sup>2</sup> was constructed for less than 12  
45 months.  
46  
47  
48  
49  
50  
51

52 **Introduction**  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

1  
2  
3  
4  
5 DELTA CITY shopping mall located in Belgrade is the first building of the “shopping  
6 mall” type in Serbia, Figure 1. The Investors were companies Delta M d.o.o. and Delta City  
7  
8 mall” type in Serbia, Figure 1. The Investors were companies Delta M d.o.o. and Delta City  
9  
10 d.o.o from Belgrade. The authors of this paper were engaged with preliminary and main  
11  
12 structural design.  
13

14 The whole building is in plan functionally divided into two blocks: shopping mall and  
15  
16 multi-story open garage, Figure 2. The overall dimensions of the layout of the structure are  
17  
18 210 m × 120 m. Area in plan is around 20.000 m<sup>2</sup>, while the total gross area is appro-  
19  
20 ximately 80.000 m<sup>2</sup>, with four main levels in the mall (underground garage, ground floor,  
21  
22 first and second floor with multiplex cinema), Figure 3, and five parking levels in the open  
23  
24 garage. The storey height is 5.80 m in mall i.e. half of it, 2.90 m in open garage. The  
25  
26 common continuous foundation slab is positioned at 5.1 m below the level of the surroun-  
27  
28 ding landscape terrain. The highest expected underground water-table is about 1.0 m  
29  
30 below terrain.  
31  
32

33  
34 Due to uneven floor height, structure mass and stiffness of the mall and the open  
35  
36 garage, as well as different exposure conditions during service life, garage structure is  
37  
38 separated from the mall structure by vertical expansion joint 20 cm wide along the entire  
39  
40 structure height, except at the foundation level.  
41  
42  
43

## 44 45 **Shopping mall structure**

### 46 47 48 49 50 **Building description**

51  
52  
53  
54 In general, the building is organized at orthogonal grid at spacing of 8.2 m in both  
55  
56 directions. Due to irregular shape of the layout, this grid is inevitable disturbed around the  
57  
58  
59  
60  
61  
62  
63  
64  
65

1  
2  
3  
4  
5 perimeter. Three main atriums (A-C) and curved pedestrian passages additionally impair  
6 the simplicity of the layout, as well as in-plane stiffness of the slabs, Figure 4. At ground  
7 level, the curved colonnade of columns turns into the orthogonal column layout in the  
8 underground garage, by means of heavy cast in place transfer structure.  
9

10  
11  
12  
13  
14 Above the ground level, three cascaded floor slabs rise from east to west, ending with  
15 the highest part of the building - six cinema halls at north-west side of the building, Figure  
16  
17  
18 1. The cinema is a steel structure, with each of halls completely isolated against vibrations  
19 by means of "Sylomer" pads.  
20  
21

22  
23 Asymmetric floors are supported by grid of columns of constant cross-section 60 cm x  
24 80 cm in the underground garage, 60 cm x 60 cm above ground level and 40 cm x 60 cm  
25 in façade along with stair-shafts (ST) mainly positioned close to the perimeter of the  
26 building, Figure 4. The height of the columns above the ground level is 11.6 m - 17.4 m.  
27  
28  
29

30  
31  
32 Perimeter retaining 40 cm thick wall together with foundation slab and slab at ground  
33 level acts as a stiff base box, providing the horizontal supports to cantilevered columns.  
34  
35

36 The structure is designed for XC1 exposure class and 90 min fire resistance.  
37  
38  
39  
40

#### 41 Construction and structure concept 42 43 44

45 From the very beginning, the RC/PT hybrid structural concept of precast floors and cast  
46 in place columns/stair-shafts was adopted as an optimal solution which should provide  
47 cheap and fast construction, and later on easy maintenance.  
48  
49

50  
51  
52 Two options of construction sequences were analyzed: upward floor-by-floor progress-  
53 ing, with cranes positioned at the perimeter and inside the building, and, frame-by-frame of  
54 complete height methodology, moving from west to east. The former solution was finally  
55 adopted by Contractor.  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

1  
2  
3  
4  
5 Dealing for the first time with such a large layout, the permanent expansion joint across  
6  
7 the middle of the mall building was suggested, with two blocks of about 100 m in length.  
8  
9 However, appreciating Architects' vast world-wide experience, the structure was finally  
10  
11 designed without permanent expansion joints. To compensate for thermal movements  
12  
13 during bare structure construction, structure above foundation was temporarily divided in  
14  
15 three free blocks, with expansion joints to be closed after closing of building envelope,  
16  
17  
18 Figures 5-6. Ground floor slab of somewhat larger eastern block was temporarily  
19  
20 horizontally disconnected from the perimeter retaining wall as well, wherever it was  
21  
22 possible.  
23  
24  
25  
26

#### 27 Spatial frame concept

28  
29  
30  
31  
32 Due to, for temperature effects unfavorable position of stair-shafts along perimeter of  
33  
34 the building, as well as questionable transfer of wind/seismic forces from patchwork of  
35  
36 floor slabs to stair-shafts with low axial loading, the spatial frame concept of the structure  
37  
38 was adopted, without shear walls or bracings. All façade elements and partitions made at  
39  
40 large from "Ytong" blocks were designed to accommodate for building thermal  
41  
42 movements.  
43  
44

45 The stairs and lift-shafts were designed as less stiff framed towers with precast flights,  
46  
47 although wall-box concept with slab expansion joint around the core was also possible  
48  
49 solution. Together with about 250 cantilevered columns with height/width ratio of about 20,  
50  
51 those medium-ductile vertical elements were capable to provide enough load capacity in  
52  
53 the case of 475 year return period earthquake, with low ground acceleration of 12% of  
54  
55 gravity, but horizontal displacements were excessive yet.  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

1  
2  
3  
4  
5 For displacement control, the full moment resisting frames, with beams cast in place as  
6 well were introduced. The basic so-called "seismic frames" were positioned in plane of  
7 external/internal façade frames, to increase building torsional stiffness, as well as to avoid  
8 local torsion problems due to eccentric connection of precast slabs and façade beams,  
9  
10 Figure 7. In course of structure stiffness optimization, few transverse frames were added  
11 to the west side, where the concentration of building mass was more pronounced.  
12  
13  
14  
15  
16  
17  
18

19 In preliminary design stage, a full-precast concept of seismic frames was examined as  
20 well. The advantage of cast in place columns was that it was easy to provide continuation  
21 of precast simple beams by adding as much as needed upper reinforcement over columns  
22 – for additional gravity loads precast beams could act as continuous beams. If, for the  
23 earthquake load the sign of the resulting support bending moments is changed, lack of  
24 lower reinforcement continuity will result in potential beam plastic hinges developed on  
25 only one side of the span – not usual, but might be useful enough. However, being  
26 positioned mainly in façade with narrow columns and façade eccentrically loaded beams  
27 susceptible to torsion as well, the cast in place moment resisting frame concept was finally  
28 adopted.  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42

#### 43 Floor structure

44  
45  
46  
47 The 80 cm thick floor structure comprises:

- 48 - precast and semi-precast (temporarily propped) RC beams in longitudinal – east-  
49 west direction, supported by column corbels through steel leveling pads and 25 mm  
50 thick layer of non-shrinking mortar, Figures 8-9;  
51  
52
- 53 - prestressed hollow-core slabs (HCS) of 20-35 cm in depth, supported through  
54 EPDM strip by lateral continuous beam corbels. At beam ends, lateral corbels were  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

1  
2  
3  
4  
5 designed in form of fork, to provide HCS support over the width of the column and  
6  
7 lateral formwork for column at the same time, Figure 8;

- 8  
9
- 10 - RC topping of 7.5 cm in depth with wire fabric;
  - 11
  - 12 - transversal in-plane stiffening RC ties in line of every second-third column with  
13  
14 depth equal to adjacent HCS depth, which together with HCS, edge beams and  
15  
16 topping create in plane stiff floor diaphragm.  
17

18  
19 Where precast concept wasn't applicable, the RC cast in place structures were applied,  
20  
21 Figure 4.

22  
23 Introduction of seismic moment resisting frames allowed all other, the majority of beams  
24  
25 to be designed as RC precast simple beams, with minimum upper axial continuation  
26  
27 reinforcement –  $2\phi 25$  bars, passing through the columns cast in place. At preliminary  
28  
29 stage, all beams were designed as precast prestressed elements but, when later on storey  
30  
31 height was increased, the RC concept was adopted to enable local precast contractors to  
32  
33 bid too.  
34  
35

36  
37 Connection of precast HCS and cast in place narrow façade beams – seismic frames  
38  
39 was initially designed as so-called "indirect support" detail, with temporary props, Figures  
40  
41 10-11. The main reason was to eliminate the beam corbels and to produce monolithic  
42  
43 connections that might resist torsion. Without any previous experience with such  
44  
45 connection details, some literature/practice research was conducted and the *fib* Bulletin 6<sup>1</sup>  
46  
47 was used as a reference document. Precast contractors engaged in this project didn't  
48  
49 have such an experience as well, but they were ready to accept designers solution if  
50  
51 experiments validated it.  
52  
53

54  
55 Domestic law claims that new technologies should be verified by testing, so experi-  
56  
57 ments were organized at IMS Institute in Belgrade according to program prepared by  
58  
59 designers, with full support and understanding of the Client, Figure 12. The HCS of 20 cm  
60  
61  
62  
63  
64  
65



1  
2  
3  
4  
5 in depth plus topping of 7.5 cm, with all six or four cores filled with concrete at 1.2 m in  
6  
7 length were tested. Initially, two levels of end restraints were planned for testing: "no  
8  
9 torsion stiffness" of edge beam (HCS as a simple beam) and "indefinite torsion stiffness" of  
10  
11 edge beam (fully fixed support of HCS). Unfortunately, the testing of more interesting fixed  
12  
13 model was abandoned; the site couldn't wait for those results.  
14

15  
16 According to *fib* Bulletin 6<sup>1</sup>, the shear at interface between HCS and cast in place edge  
17  
18 beam was governing design criteria in case of simple beam model, so the inclined bars  
19  
20 were added in each opened core, Figures 10-11. Experiments verified the calculations -  
21  
22 four reinforced cores were enough for required ultimate capacity of indirectly supported  
23  
24 HCS in this case. The mode of failure was predominantly flexural, controlled by the  
25  
26 amount of lower reinforcement in the cores, although some splitting between topping and  
27  
28 HCS was also observed, Figure 13. Pull-out of new concrete from the cores was not  
29  
30 noticed.  
31  
32

33  
34 Because the experiments were not fully completed and there was no time to wait on  
35  
36 their completion, traditional longitudinal beam corbel was returned into construction. At  
37  
38 limited length, the indirect support concept was however applied; designers were confident  
39  
40 that this solution will be verified. The behavior of this connection has been monitored since  
41  
42 the construction time and it was proven satisfactory.  
43  
44

45  
46 Irregular parts of the floors were designed as cast in place structures, with appropriate  
47  
48 connections with precast elements, Figure 14. At main entrance area, four composite  
49  
50 columns-towers dominate; each comprises three steel tubes  $\phi 400$  mm filled with concrete.  
51  
52 Two of three tubes bypass the first indented floor and support the second floor slab, and  
53  
54 all three carry the roof edge. The "piano-shaped" first floor is hanging from the second  
55  
56 floor, Figure 14.  
57  
58  
59  
60  
61  
62  
63  
64  
65

1  
2  
3  
4  
5 The designers were persistent in exploiting precast concept. So, the floor of fast-food  
6 and cinema complex was designed as assemblage of HCS and precast beams as well,  
7 with some stiffening RC beams where it appeared inevitable. The "Sylomer" anti-vibration  
8 pads of the steel frame supports were anchored into topping of increased thickness,  
9  
10 Figure 15, or into the RC stiffening – transfer beams.  
11  
12  
13  
14  
15  
16  
17  
18

#### 19 Foundation and underground garage

20  
21  
22  
23 At foundation level, building enters deposits of refueled sand, deformable clay-sandy  
24 dust and organic clay. Since these layers usually have low and uneven characteristics, it  
25 was necessary to replace about 0.6 m of natural soil material with a tampon layer made of  
26 compacted crashed stone and gravel.  
27  
28  
29  
30  
31

32 The foundation structure of 210 m x 120 m in plan comprises 40 cm thick flat plate with  
33 inverted drop-panels, without any expansion joints, Figure 16. This concept makes earth  
34 and water-proofing membrane works easier, especially if underground water-table is close  
35 to the level of the foundation, as expected to be during construction. The space between  
36 drop-panels was filled with compacted gravel and sand with thin concrete pavement on the  
37 top. Such a layered system allow easy creation of pavement slopes required in unde-  
38 rground garage and easy placing and maintenance of rain and technical water pipe-lines.  
39 At the same time, it greatly helps slab thermal insulation and serves as additional ballast  
40 against lift-up of light building in case of extreme water-tables.  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51

52 During construction, the underground water table wasn't too high; still it was necessary  
53 to slightly lower it by means of temporary partial drainage system and water pumping. If  
54 the extreme underground water however occurred, the complete flooding of the  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

1  
2  
3  
4  
5 underground level was considered. The large concrete slab was poured in blocks of 16.4  
6  
7 m x 16.4 m, of checked pattern to compensate for shrinkage movements.  
8  
9

10 The huge underground garage volume is prone to substantial seasonal temperature  
11 changes, due to the presence of two entrances and large smoke exhausters around the  
12 garage perimeter. To avoid thermal problems of mall ground level slab without bottom  
13 thermal insulation, the used heated mall air, instead to be exhausted into the surrounding,  
14 has been returned from the roof down into the garage space.  
15  
16  
17  
18  
19  
20  
21  
22

### 23 Structural analysis and design 24 25 26

27 With a structural concept and main details defined, the analysis was conducted at five  
28 stages:  
29  
30

- 31 - analysis of isolated elements such as HCS, precast beams, corbels etc. for local  
32 loadings of gravity type;  
33
- 34 - analysis of complete, finished structure, including isolated elements as a spatial 3D  
35 framed structure for the effects of gravity, wind, temperature, shrinkage and  
36 earthquake loads. For those analysis, 3D Etabs model of the structure was created  
37 modeling all specifics of this hybrid structure, including particular connections of  
38 elements;  
39
- 40 - analysis of, by temporary expansion joints separated parts of the bare structure  
41 during construction stage;  
42
- 43 - analysis of the final temperature and shrinkage effects taking into account effects  
44 induced in parts of the structure before closing of temporary expansion joints (initial  
45 stage), superimposed to effects to be further developed in the complete structure  
46 from joint closing time onward;  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62

1  
2  
3  
4  
5 - analysis of in-plane diaphragm strength and stiffness of precast floor.  
6

7 All superimposed ( $1.0 \text{ kN/m}^2$  -  $5.0 \text{ kN/m}^2$ ) and live loads ( $3.0 \text{ kN/m}^2$  -  $7.5 \text{ kN/m}^2$ ) were  
8 defined by Architect, according to world-wide practice for this type of buildings.  
9

10 Taking into account construction schedule and long-term measurements of local  
11 temperatures, structure was analyzed for temperature change of  $\pm 25 \text{ }^\circ\text{C}$  in the construction  
12 stage. Although it was suggested to designers that, after closing of building envelope no  
13 further temperature changes were possible (building is acclimatized during service), the  
14 whole structure was checked for accidental temperature change of  $\pm 10 \text{ }^\circ\text{C}$ . As a result, the  
15 bending capacity of perimeter columns was slightly increased.  
16  
17  
18  
19  
20  
21  
22  
23  
24

25 The earthquake effects were analyzed according to Eurocode 8<sup>2</sup>, for ground of class B,  
26 peak base-rock acceleration of 12% of acceleration of gravity and behavior factor of  $q=4,0$ .  
27 Multi-modal analysis, combining effects from two directions, was conducted, along with  
28 control of columns for bi-axial bending and shear<sup>2</sup>.  
29  
30  
31  
32  
33

34 The main issue was optimization of number and position of seismic – moment resisting  
35 frames for control of lateral deflections, especially in plane of facade. In preliminary stage,  
36 the main façade was designed with the use of precast RC vertical panels, to allow  
37 anchorage of ceramic-façade elements. After series of consultations with façade  
38 contractor, façade steel rails were finally anchored directly into the "Ytong" block elements,  
39 which greatly helped in overall structure behavior, Figure 17.  
40  
41  
42  
43  
44  
45  
46  
47

48 According to domestic regulations, the main design comprises all the necessary for  
49 construction details – shop drawings, quite a job in the case of hybrid structures of this  
50 kind.  
51  
52  
53

## 54 55 56 **Multi-story garage structure** 57 58 59 60 61 62 63 64 65

1  
2  
3  
4  
5 Structure description  
6  
7  
8  
9

10 The structure of the open multi-story garage is separated from the mall structure by  
11 vertical expansion joint 20 cm wide along the entire structure height, except at the  
12 foundation level. As mentioned before, a common foundation slab is designed for both  
13 separated structures, with reinforced concrete retaining wall in the façade plane at the  
14 underground level.  
15  
16  
17  
18  
19

20  
21 The overall dimensions of the garage structure layout are 96.0 m × 32.0 m. The garage  
22 has five above-ground parking levels with storey height of 2.9 m, and four one-way ramps  
23 for inter-level traffic. To minimize restraint forces induced by temperature changes, the  
24 structure is divided by expansion joint in axes 16 into two separated parts along the entire  
25 height, except at the foundation level, Figure 18.  
26  
27  
28  
29  
30  
31

32 The garage structure differs from the mall's structure in a way that all RC frames are  
33 cast in place moment resistant frames. Due to the total allowable height for the floor  
34 structure of 65 cm, it was not possible to apply RC precast simple beams. Besides, as it  
35 was possible to locate the shear walls at proper positions, the structure was designed as a  
36 combination of RC frames and RC shear walls.  
37  
38  
39  
40  
41  
42

43 The main structure consists of: precast prestressed HCS floor structure, with 10 cm  
44 reinforced concrete topping; cast in place reinforced concrete transverse frames in shorter,  
45 north-south direction at a distance of 8.2 m, and reinforced concrete shear walls cast in  
46 place, in both directions. Shear walls were designed to resist wind and seismic lateral  
47 loads and in the larger, western part are located near the center of the garage layout, to  
48 prevent a significant restraint forces from temperature related volume changes. Ramps  
49 and some parts of the floor structure geometrically irregular in plan were designed as  
50 reinforced concrete slabs cast in place, Figure 18. Beams of the frames were cast in two  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

1  
2  
3  
4  
5 phases: in the first phase the lower half of the beams was cast, and in the second phase,  
6  
7 after the hollow core slabs were mounted, the upper half of the beams, together with  
8  
9 topping, was cast in place.

10  
11 The floor structure was designed as a hybrid structure. Although the shear interface  
12  
13 reinforcement between the precast slabs and in situ topping necessary for composite  
14  
15 action was not required, the reinforcement loops projecting into topping were concreted  
16  
17 into the longitudinal joints between precast slabs at every 1.5 m –2.0 m.  
18  
19

20  
21 To provide for rigid floor diaphragm action of a composite floor, reinforced joints  
22  
23 between precast slabs and cast in place beams were made. Reinforcement along the  
24  
25 perimeter of such formed composite slabs was designed for resisting the internal forces in  
26  
27 rigid diaphragm, Figure 19. Besides, the additional steel ties were provided in longitudinal  
28  
29 direction for connecting the composite slabs and vertical structural elements, to provide  
30  
31 the entire structural integrity and secondary bearing system in the direction in which  
32  
33 frames did not exist. At the connection of composite floor structure and shear walls which  
34  
35 resist the lateral loads, the reinforcement for shear force transfer was designed.  
36  
37

38  
39 The foundation slab was designed as a solid flat slab 105 cm thick, with upper surface  
40  
41 65 cm lowered in relation to the mall's foundation slab, for providing room for electrical  
42  
43 installations situated in this area of the underground garage.  
44

45  
46 The structure was analyzed and designed for following loads: gravity loads, lateral  
47  
48 loads (seismic and wind loads), car impact on the barriers and temperature changes of -  
49  
50 32<sup>0</sup> C and +20<sup>0</sup> C for all the slabs, except for the top level slab which was under direct  
51  
52 sunlight and exposed to +40<sup>0</sup> C temperature change. Besides, the structure was designed  
53  
54 for XD3 exposure class and 90 minutes fire resistance. As expected, temperature related  
55  
56 volume changes were the governing criteria in reinforced concrete frame design.  
57

58  
59 Durability requirements  
60  
61  
62  
63  
64  
65

1  
2  
3  
4  
5  
6  
7  
8 Special attention in design was paid to durability requirements. The main factors  
9  
10 affecting open parking structure durability are restraint to volume changes, deterioration  
11  
12 from freeze-thaw cycles and corrosion damage from chloride exposure<sup>3</sup>. The resistance to  
13  
14 volume changes due to shrinkage, creep and temperature variations induces forces which  
15  
16 can cause cracking, especially in joints between precast and cast in place structural  
17  
18 elements. In Belgrade climate seasonal and even daily temperature variations can be very  
19  
20 high, freezing can occur and deicing salts are often used in winter. Deicing salts are  
21  
22 carried with snow and ice on the undersides of the vehicles. The salty water that melts  
23  
24 from cars falls on the floor, often accumulating on surface depressions. The chloride  
25  
26 moisture seeps into the concrete, and if the concrete surface is cracked, chlorides can  
27  
28 rapidly penetrate the slab.  
29  
30

31  
32 That is why according to Eurocode 2<sup>4</sup> open parking structures should be designed for  
33  
34 the exposure class XD3, which is the class with the rigorous requirements regarding  
35  
36 adequate durability insurance. Even more, special measures can be required to ensure  
37  
38 adequate structural durability for class XD3 in open parking structures.  
39  
40

41 So, the garage structure was designed for exposure class XD3 and following measures  
42  
43 were undertaken to provide adequate durability: good quality, air-entrained concrete of  
44  
45 class C32/40 for all cast in place structural elements, proper drainage of the parking slabs  
46  
47 with 1.5 percent slope to eliminate the ponding water, minimum concrete cover of 4.5 cm  
48  
49 for all reinforced concrete elements and 5.5 cm for prestressed hollow core slabs, limited  
50  
51 crack width for reinforced concrete elements and decompression limit for prestressed  
52  
53 hollow core slabs, protection of all steel elements not protected by concrete by  
54  
55 anticorrosive agents, high-quality sealants at construction and expansion joints, special  
56  
57 quality control of all workmanships, especially of works done in situ. Since the cracks in  
58  
59  
60  
61  
62  
63  
64  
65

1  
2  
3  
4  
5 parking cast in place slabs could not be avoided, even for gravity loads, the traffic-bearing  
6  
7 membranes which consisted of a multi-layer elastomeric polyurethane material with an  
8  
9 integral, nonskid traffic topping were provided. These water and wear resistant  
10  
11 membranes protect the parking slabs against deterioration and leakage and are capable of  
12  
13 bridging the small cracks, up to 0.2 mm width, Figure 20.  
14

15  
16 During the service life, a care should be taken on the structure conditions and its  
17  
18 maintenance. It is performed by regular cleaning and inspections of various structural  
19  
20 elements and immediate repair upon detection of any damage, as well as by periodical  
21  
22 replacement of sealants and membranes, all of which is defined in a separate  
23  
24 maintenance project.  
25  
26

## 27 28 29 **Conclusion**

30  
31  
32  
33  
34 The massive use of prestressed hollow-core slabs on the first project of this kind in  
35  
36 Serbia was valuable experience for all participants:

37  
38 - in general, architects and MEP consultants don't like hollow-core floors – they are  
39  
40 forced to define and coordinate major floor openings much earlier than usually. As  
41  
42 expected, some openings were opened later on, on the site;  
43  
44

45  
46 - HCS producers - contractors usually define strength, deflections and fire resistance of  
47  
48 HCS in their catalogs. What designers and sub-contractor need to know is how to hang  
49  
50 MEP installations, how to open a new opening in the floor, how to connect partitions and  
51  
52 alike;  
53

54  
55 - structural engineers need some more sophisticated tools for more precise analysis of  
56  
57 HCS with various openings and specific loading patterns. Indirect support connection of  
58  
59  
60  
61  
62  
63



1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

HCS with cast in place and semi precast beams, or with already finished walls (jump-form technology) is one of the still not well understood issues in HCS usage.

Nevertheless, the challenging structure was completed in one year, with due appreciation of Client and Architect.

**Acknowledgement**

The authors would like to thank to all participants in this project on the succesful cooperation. Concept and preliminary architectural/MEP designs were produced by Moore Architects from Israel, while the main design was assigned to Slavija Biro d.o.o. from Belgrade. Project management was provided by MACE from UK, while real-estate issues were managed by Colliers from USA. General Contractor was company Porr from Austria, with two main sub-contractors for precast works: Širbegović Company from Bosnia and Hercegovina and Vibrobeton from Croatia. Local contractors were engaged for all of in-place works.

1  
2  
3  
4  
5 **References**  
6  
7  
8  
9

- 10 1. International Federation for Structural Concrete. *Special design considerations for*  
11 *precast prestressed hollow core floors*. FIB, Lausanne, 2000, Bulletin 6.  
12  
13  
14 2. European Committee for Standardization. *Eurocode 8: Design of structures for*  
15 *earthquake resistance - Part 1: General rules, seismic actions and rules for buildings*.  
16  
17 CEN, Brussels, 2004.  
18  
19  
20  
21 3. Precast/prestressed Concrete Institute. *Parking structures: Recommended practice for*  
22 *design and construction*. PCI, Chicago, 1997.  
23  
24  
25 4. European Committee for Standardization. *Eurocode 2: Design of concrete structures -*  
26 *Part 1-1: General rules and rules for buildings*. CEN, Brussels, 2004.  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

1  
2  
3  
4  
5 **List of figures**  
6

7  
8 Figure 1 Aerial view  
9

10 Figure 2 Mall and garage blocks  
11

12 Figure 3 Schematic vertical cross section  
13

14 Figure 4 Layout of the mall structure at the level of the first floor  
15

16 Figure 5 Layout of temporary expansion joints  
17

18 Figure 6 Details of temporary expansion joints at façade  
19

20 Figure 7 Layout of cast in place seismic moment resisting frames  
21

22 Figure 8 Typical HCS-precast beam-column detail  
23

24 Figure 9 Mall structure under construction  
25

26 Figure 10 Concept of HCS-cast in place beam indirect support  
27

28 Figure 11 Detail of indirect support in construction  
29

30 Figure 12 Laboratory experimental setup for HCS indirect support testing  
31

32 Figure 13 Vertical crack on HCS-beam connection prior to failure  
33

34 Figure 14 Cast in place slabs and composite columns at mall main entrance  
35

36 Figure 15 Detail of cinema steel frame-HCS connection through "Sylomer" pads  
37

38 Figure 16 Checked pattern of foundation slab in construction  
39

40 Figure 17 Anchorage of ceramic-tiles façade directly into "Ytong" blocks  
41

42 Figure 18 Layout of the garage structure  
43

44 Figure 19 Joints between HCS and cast in place beams in garage  
45

46 Figure 20 Setting waterproof membranes in garage  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65

Figure 1  
[Click here to download high resolution image](#)



Figure 2  
[Click here to download high resolution image](#)




Figure 3  
[Click here to download high resolution image](#)




Figure 4  
[Click here to download high resolution image](#)




Figure 5  
[Click here to download high resolution image](#)






Figure 6  
[Click here to download high resolution image](#)




Figure 7  
[Click here to download high resolution image](#)




Figure 8  
[Click here to download high resolution image](#)



Figure 9  
[Click here to download high resolution image](#)



Figure 10  
[Click here to download high resolution image](#)




Figure 11  
[Click here to download high resolution image](#)



Figure 12  
[Click here to download high resolution image](#)



Figure 13  
[Click here to download high resolution image](#)






Figure 14  
[Click here to download high resolution image](#)



Figure 15  
[Click here to download high resolution image](#)



Figure 16  
[Click here to download high resolution image](#)



Figure 17  
[Click here to download high resolution image](#)



Figure 18  
[Click here to download high resolution image](#)




Figure 19  
[Click here to download high resolution image](#)



Figure 20  
[Click here to download high resolution image](#)







Author 2 photo  
[Click here to download high resolution image](#)



Author 3 photo  
[Click here to download high resolution image](#)



Author 4 photo  
[Click here to download high resolution image](#)

